



STORMWATER DRAINAGE AS-BUILT REQUIREMENTS FOR PRIVATE SITE DEVELOPMENT

1. State plane coordinates on all catch basins, junction boxes and pond structures.
 - a. (Reference NAD-83 for Horizontal control)
 - b. (Reference NAVD-88 for Vertical control)
2. Identify all ditches, outfalls and receiving water bodies.
3. Rim and invert elevations on catch basins, junction boxes, pond structures and drainage swales.
4. Description of pipe, length and size.
5. North arrow and scale.
6. All drainage ponds easements and who it is maintained by, if applicable.
7. Show all drainage easements and its size.
8. Best Management Practices (BMP), type/description, and location.
9. Contractor contact information.
10. Developer contact information
11. Date of construction.
12. Water and Sanitary Sewer Services - Location of services, type of pipe, size and length.
13. Impervious area of site.